

Pequest Wildlife Management Area / Kenco Acquisition

Presented by:



AMY S. GREENE
ENVIRONMENTAL
CONSULTANTS^{INC.}



NEW JERSEY DIVISION OF
Fish and Wildlife



North Jersey
Resource
Conservation
and
Development

Kenco Wetland Restoration Project

Overview

- 90+ Acre Property, Modified Agricultural Wetlands
- Drained in the 1950s for agriculture production
- Over 1-Mile of Shoreline on the Pequest River
- Over 3 miles of agricultural ditch systems
- 21 acres of mature forest
- Dominant vegetation included sod (grass species), invasive species (autumn olive, multiflora rose)



Site: before

Ditch draining the site



Site: before

Ditch draining the site (central portion): pre-grading
Note cattails, trash, and Autumn Olive



Preconstruction Conditions- View North



Pequest Riparian Shelf: before

Access road, taken during wetland delineation, pre-grading



Site: Pre-construction

Looking south along the piques, note access road in the riparian zone, Autumn Olive in the passive forest, ditching in the wetland



View of Agricultural Drainage and Roadways

Kenco Project Timeline

- NJ Wetland Mitigation Council Resolution and Funding- *August 2014*
- Design and NJDEP Permitting- *2014-2017*
- Start of Construction- *July 2017*
- Start of Planting- *November 2017*
- Completion of Planting- *March 2018*
- Start of Maintenance and Monitoring- *April 2018*
- Anticipated Project Closeout – *December 2022*



Pre-restoration Fish Sampling

NJDFW Freshwater Fisheries- Baseline Inventory



Mussel Survey

Permit requirement- baseline inventory

Design Highlights

- 34.2 acres of Forested Wetland Restoration
- 19.6 acres of Wet Meadow Restoration
- 9.1 acres of Stream Corridor Restoration (nearly 2 miles)
- 21 acres of enhanced Forested Wetlands
- 4.6 acres of Passive Forested Wetland Restoration
- Apprx. 1-mile of Floodplain Bench along the Pequest River
- Apprx. 1-mile of stream realignment
- Ditch plugging
- Instream structures and bank stabilization (log/rock vanes, revetment)
- Wildlife Habitat features (snags, brushpiles, turtle nesting mounds)







[illegible]

Shrub (100 stems per plot)	Swamp white oak	Swamp black oak	8-10 ft.	10-12 ft.
sky dogwood	<i>Cornus amomum</i>	<i>Cornus amomum</i>	10-12 ft.	10-12 ft.
slenderberry	<i>Amelanchier canadensis</i>	<i>Amelanchier canadensis</i>	10-12 ft.	10-12 ft.
swamp hawthorn	<i>Viburnum dentatum</i>	<i>Viburnum dentatum</i>	10-12 ft.	10-12 ft.
vineberry	<i>Vitis rotundifolia</i>	<i>Vitis rotundifolia</i>	10-12 ft.	10-12 ft.
black chokeberry	<i>Aronia melanocarpa</i>	<i>Aronia melanocarpa</i>	10-12 ft.	10-12 ft.
white hazel	<i>Alnus incana</i>	<i>Alnus incana</i>	10-12 ft.	10-12 ft.
sky dogwood	<i>Cornus amomum</i>	<i>Cornus amomum</i>	10-12 ft.	10-12 ft.
slenderberry	<i>Amelanchier canadensis</i>	<i>Amelanchier canadensis</i>	10-12 ft.	10-12 ft.
swamp hawthorn	<i>Viburnum dentatum</i>	<i>Viburnum dentatum</i>	10-12 ft.	10-12 ft.
vineberry	<i>Vitis rotundifolia</i>	<i>Vitis rotundifolia</i>	10-12 ft.	10-12 ft.
black chokeberry	<i>Aronia melanocarpa</i>	<i>Aronia melanocarpa</i>	10-12 ft.	10-12 ft.
white hazel	<i>Alnus incana</i>	<i>Alnus incana</i>	10-12 ft.	10-12 ft.

Side View

Diagram illustrating a stone stage on a ditch fill. The stage is labeled "STONE STAGE" and has a width of 2m and a height of 1m. The top of the bank is indicated by a dashed line. The ditch fill is labeled "DITCH FILL".

TYPICAL DITCH FILL PROFILE
RTB



Construction Highlights

- Sediment and Erosion Control /BMP's
- Over 40,000 CY of Earth Movement
- Topsoil Stripping and Reuse
- Removal of Debris (irrigation, pipes, drainage)
- Stream Diversion
- Decompaction and Microtopography
- Plant Salvage



Excavation of Streams



UNT Realignment- In Progress



Stream Restoration Construction



Stabilized Stream Realignment with Plant Salvage



Debris Removal



Bank Stabilization- Rock Vanes




Log Vanes Installed within the Pequest River



Decompaction prior to seeding.

INVASIVE SPECIES MANAGEMENT ON RESTORATION SITES

- Excavation and new soil - Eliminates plant, seed source , seed bank (\$\$\$)
- Mowing
- Change in Hydrology- alterations of habitat
- Herbicide Application- selective/non-selective
- Shading and Outcompeting with desirables



Woody Invasive Management- Preconstruction

Autumn Olive, Multiflora Rose



Cut and Stump Spray Treatment within Passive Forest Restoration




Clearing, Grubbing, Excavation, and Burying of Invasives

New Topsoil, and Seeding with Invasives



Seeding and Stabilization with Native Species



Grassland Meadow Invasive Species

Turf, Autumn Olive, Mugwort, Canada Thistle, Green Foxtail



Site Wide Mow and Herbicide Application- Soil Sterilization



Original Treatment Fall 2015
Second Treatment Summer - 2017



2018- Nearly 100 % Coverage of Foxtail

Goal to have Warm Season Grasses outcompete Foxtail in future years.



Change in surface water aids in the control of invasive species!

Sometimes creates new problems (Common Reed or Reed Canarygrass)

Landscaping Highlights

- Plant Salvage
- Over 20,000 trees and shrubs installed
- 70 acres seeded and stabilized with native seed mixtures
- Habitat features (brush piles, perching snags, vernal habitat, basking logs, turtle nesting mounds)



Bareroot Seedlings- NJ State Nursery



Live Stakes- harvested onsite, locally



Containerized trees and shrubs- Pinelands Nursery, NJ



Habitat Features- Brushpiles



Wood Turtle Nesting Mounds



Realigned UNT of the Pequest River- plant salvage



Wet meadow- grassland bird habitat



Vernal Habitat- basking logs, snags



Pequest Riparian Shelf: before

Looking north, access road



Pequest Riparian Shelf: after



Pequest Riparian Shelf: after



Pequest River Bank: before



Pequest River Bank: before

Note heavy erosion



Pequest River Bank: after



Restored Stream: after

MIM's forest in the back



Realigned Stream-

September 2018



Tree establishment near vernal habitat

Maintenance and Monitoring

- Annual Monitoring (2018-2022)
- Invasive Species Control
- Wildlife documentation
- Replanting
- Herbivory Control (Deer, beaver, voles)
- Public Access
- Educational Signage and trail



Rare Plants and Wildlife

Juncus toreyii (NJ State Endangered)



Monarch Butterfly

On swamp milkweed



2018 Post-construction Fall Monitoring



2018 Post-construction Fall Monitoring



Parking Lot Completion

For fishing, hunting, and public access



2018 Construction Completion

Aerial View of Restoration Site Showing Forested Wetland, Wet Meadow, Riparian Zone, Restored Stream Channels and Floodplain Bench along Pequest River